

**INSTALLATION NOTES:**

**IT IS RECOMMENDED TO PRE DRILL HOLES WHEN ATTACHING THE TRIM AS TO AVOID SPLITTING ANY OF THE MOLDING. USE FINISH NAILS & GLUE. (RENTING A BRAD GUN IS A GOOD IDEA AND YOU WON'T NEED TO PRE-DRILL HOLES.)**

**TOTAL STACK HEIGHT: 7-7/16"**

**INSTALL WALL TO WALL FIG: 1**

1. INSTALL CLEAT #1 – 1/2" BACK FROM FACE FRAME (CUT TO SIZE.)
2. GLUE & NAIL (VFR8 TO TOP OF CABINETS (CUT TO SIZE.))
3. INSTALL TF396 (CUT TO SIZE.) NOTE! THERE IS A 1/16" SPACE BETWEEN #1 CLEAT & TF396 (NEEDS TO BE (SHIM): A PIECE OF MATERIAL USED TO FILL IN THE SPACE.)
4. INSTALL TF396.
5. INSTALL VFR8 ON TOP OF TF396.
6. INSTALL CLEAT #2 & #3 (CUT TO SIZE)
7. ATTACH SWVCRM8 TO CLEAT #3 (CUT TO SIZE)

