

INSTALLATION NOTES:

IT IS RECOMMENDED TO PRE DRILL HOLES WHEN ATTACHING THE TRIM TO AVOID SPLITTING ANY OF THE MOLDING. USE FINISH NAILS & GLUE.

TOTAL STACK HEIGHT: 4-5/16"

INSTALL WALL TO WALL

1. INSTALL CLEAT TO TOP OF CABINET - FRONT OF CLEAT FLUSH WITH FRONT OF FACE FRAME.
2. INSTALL VFR8 ON TOP OF CABINET - PULLED 3/4" TO BOTTOM OF TF396FH.
3. INSTALL TF396FH/VFR8 TO TOP OF VFR8 - FRONT OF TF396FH PULLED TO LIP OF CLEAT.
4. INSTALL SCM8 TO FRONT OF TF396FH - TOP OF SCM8 PULLED 3/4" ABOVE TOP OF TF396FH.
5. INSTALL GREEKM TO FRONT OF TF396FH - TOP OF GREEKM ALIGNED TO BOTTOM OF SCM8.

