

INSTALLATION NOTES:

IT IS RECOMMENDED TO PRE DRILL HOLES WHEN ATTACHING THE TRIM TO AVOID SPLITTING THE MOLDING. USE FINISH NAILS & GLUE.

TOTAL STACK HEIGHT: 3-11/16"

INSTALL WALL TO WALL

1. INSTALL TSTM ON TOP OF CABINET - PULLED 3/4" TO BE FLUSH WITH THE FRONT OF CABINET DOOR.
2. INSTALL CLEAT TO TOP OF TSTM. FRONT OF CLEAT SHOULD BE PULLED BACK THE DEPTH OF A LB2.
3. INSTALL LB2 TO TOP OF TSTM - FRONT OF LB2 BACK 1/2" FROM FRONT OF TSTM.
4. INSTALL SWCRM8 TO FRONT OF LB2 - TOP OF SWCRM8 PULLED UP FROM TOP OF LB2 AS NEEDED FOR FIELD CONDITIONS.
5. INSTALL BRAIDM TO FRONT OF LB2 - TOP OF BRAIDM ALIGNED TO BOTTOM OF SWCRM8.

