

Installation Instructions – STKMLD18

INSTALLATION NOTES:

IT IS RECOMMENDED TO PRE DRILL HOLES WHEN ATTACHING THE TRIM TO AVOID SPLITTING THE MOLDING. USE FINISH NAILS & GLUE.

TOTAL STACK HEIGHT: 4-1/16"

INSTALL WALL TO WALL

1. INSTALL CLEATS FLUSH TO FRONT EDGE OF CABINET FACE FRAME.
2. INSTALL VFR8 ON TOP OF CABINET - PULLED 3/4" TO BOTTOM OF TF396FH.
3. INSTALL TF396FH/VFR8 TO CLEATS.
4. INSTALL SCM8 TO FRONT OF TF396FH - TOP OF SCM8 PULLED UP FROM TOP OF TF396FH AS NEEDED FOR FIELD CONDITIONS.

