

**INSTALLATION NOTES**

**IT IS RECOMMENDED TO PRE DRILL HOLES WHEN ATTACHING THE TRIM TO AVOID SPLITTING THE MOLDING. USE FINISH NAILS & GLUE.**

**TOTAL STACK HEIGHT: 7-11/16"**

**INSTALL WALL TO WALL**

1. INSTALL SFM8 CLEAT TO TOP OF CABINET - BOTTOM FRONT CORNER OF SFM8 ALIGNED TO FRONT OF CABINET FACE FRAME.
2. INSTALL SFM8 TO FIT FRONT OF SFM8 CLEAT - FRONT OF SFM8 TO ALIGN WITH FRONT OF CABINET DOOR.
3. INSTALL SWVCRM8 TO FRONT OF SFM8 - TOP OF SWVCRM8 PULLED UP FROM TOP OF SFM8 AS NEEDED FOR FIELD CONDITIONS.
4. INSTALL SBE8 TO INSERT POSITION OF SWVCRM8.

