

INSTALLATION NOTES

IT IS RECOMMENDED TO PRE DRILL HOLES WHEN ATTACHING THE TRIM TO AVOID SPLITTING ANY OF THE MOLDING. USE FINISH NAILS & GLUE.

TOTAL STACK HEIGHT: 1-9/16"

INSTALL WALL TO WALL

1. INSTALL CLEAT TO BOTTOM OF CABINET - FRONT OF CLEAT 1 1/4" BACK FROM FRONT OF CABINET FACE FRAME.
2. INSTALL TCM8 TO FRONT OF CLEAT.
3. INSTALL DE8 TO FRONT OF TCM8 - TOP OF DE8 ALIGNED WITH TOP OF TCM8.

